



Injector Linac Status

Masanori Satoh

(Accelerator Laboratory, KEK)

for Linac Commissioning Group

The 30th B2GM, June 18-22, 2018

Contents

1. Injector Overview
2. Progress in Phase II
3. Towards Phase III
4. Schedule: Oct. 2018 -
5. Summary




Injector overview



- Injector for light sources (PF, PF-AR) ^{3 times daily injection} and SuperKEKB
- up to 25 Hz beam repetition rate in Phase II (to save electricity)
 - 50 Hz operation in Phase III
- Thermionic e- gun for light source injection and 10 nC beam generation (e+ production)
- Photocathode rf gun for low emittance e- beam
- Flux concentrator, LAS (large aperture S-band) structure, solenoids for e+ beam capture system
- DR (damping ring) for low emittance e+ beam



Energy profile for light source and SuperKEKB injection




Progress in Phase II


- Monitors
 - High measurement precision readout ($< 10 \mu\text{m}$) and synchronized measurement for 100 beam position monitors (BPMs)
 - All data is stored together with shot id. Similar framework will be applied to pulsed magnet power supply and rf monitor data for the correlation analysis soon.
 - Wire scanner at SectorB, SectorC, Sector2, Sector3, and Sector5
 - Streak camera at Laser hut/SectorA, SectorC, and Sector3
 - RF phase/amplitude monitors for klystron, SLED, acc. structure
- Timing system for DR injection and extraction system
- Stable operation of pulsed quads and steering magnets
- Simultaneous beam injection via thermionic e- gun
- RF e- gun injection to HER (June 16th -)
- Beam energy stabilization



Pulsed magnet



DC quad (triplet)





Pulsed quad

Pulsed steering

- Pulsed quads (x28) (w/ ceramic duct) and steering magnets (x 36) on new girder (Sep. 2017 -) at Sector3 to Sector5
- Power supply stability $\sim 0.01\%$ (24 hours)
- PXI bus based local controller and cRIO
- Remote controllable mover will be ready in this summer.



Simultaneous beam operation w/ thermionic e- source





Hor. orbit

Ver. orbit

Bunch charge

Stable operation w/o significant trouble



Hor. orbit





Ver. orbit

Bunch charge






RF-Gun

0-deg QTW RF gun





Thermionic gun


90-deg CDS RF gun



e- beam from photocathode rf gun



- Redundant Yb:Fiber + Nd:YAG Hybrid Laser System
- Three oscillators
- Bunch charge
 - 3.6 nC @ first BPM
 - 2.4 nC @ Linac end
 (Phase II requirement: 1 nC)



Status




rf e- gun injection to HER

HER .115 [A] 789 [bunches]
 LER .072 [A] 789 [bunches] Luminosity Run
 Luminosity 1.814 (now) 16.342 (peak in 24H @20:34) [$10^{32}/\text{cm}^2/\text{sec}$]
 Integ. Lum. .1 (Fill) .0 (Day) .0 (24H) [/pb]

Phase 2.1.4 (200/3,200/3): 2018/06/11
 Phase 2.1.5 (100/4,100/4): 2018/06/12
 Phase 2.1.6 (200/4,100/4): 2018/06/13

6/17/2018 7:24 JST



Emittance and bunch charge status


	LER injection e+ beam		HER injection e- beam	
	Goal	Current status	Goal	Current status
Normalized emittance (Hor./Ver.) (mm·mrad)	200/40 (w/ DR)	$192 \pm 22.4 / 2.01 \pm 0.363$ @ Sector3 $185 \pm 28.4 / 1.72 \pm 0.704$ @ Sector5	150/150	<u>rf e- gun</u> $23.411 \pm 1.867/18.593 \pm 9.372$ @ SectorB $25.048 \pm 18.128/37.960 \pm 9.807$ @ SectorC $49.258 \pm 61.683/51.167 \pm 38.077$ @ Sector5 <u>Thermionic e- gun</u> e.g.) 250/100 @ Sector5
Bunch charge (nC)	0.5	1.4 (w/ flux concentrator) @ Sector5	1.0	1.0 (thermionic e- gun) @ Sector5 1.0 ~ 3.0 (rf e- gun) @ Sector5

- Phase II parameters are almost achieved.
- Horizontal emittance of e+ beam and e- emittance at BT are large.




Energy feedback, etc

- Energy feedback at J-ARC, Sector2, Sector5 for each beam operation mode (HER, LER, light source injection beam)
- Energy fluctuation at BT: $< \pm 0.1\%$
- When klystron down at Linac:
 - Beam gate close \Rightarrow waiting for recovery of klystron (8 s) \Rightarrow beam gate open



Energy Trend for HER on lcg-k2-vm:0.0

100%



Energy Trend for LER (Linac end) on lcg-k2-vm:0.0

100%



Towards Phase III


- Investigation of
 - e- beam emittance growth at BT.
 - large horizontal emittance of e+ beam
- Large misalignment at Sector2 (~ 2 mm)
 - will be fixed in this summer shutdown
- Simultaneous top up for **HER**, LER, PF, PF-AR by using **rf e- gun** and thermionic e- gun
 - Fast switching (50 Hz): rf e- gun and thermionic e- gun
- Beam position jitter issue



Pulse to pulse switching: rf e- gun/thermionic e- gun

Thermionic DC e- gun (GU_AT)

- e+ production e-: 10 nC
- e- study/HER injection: 1 nC
- PF injection: 0.3 nC
- PF-AR injection: 0.3 nC



BM_AT_J1

BM_AT_J5

RF e- gun
(GR_A1 for HER injection)

24 deg. junction line
DC bend will be replace by pulsed bend
in summer shutdown





Required injector parameters


Stage	KEKB (final)		Phase-I		Phase-II		SuperKEKB (final)	
Beam	e+	e-	e+	e-	e+	e-	e+	e-
Energy	3.5 GeV	8.0 GeV	4.0 GeV	7.0 GeV	4.0 GeV	7.0 GeV	4.0 GeV	7.0 GeV
Stored current	1.6 A	1.1 A	1 A	1 A	–	–	3.6 A	2.6 A
Life time (min.)	150	200	100	100	–	–	6	6
Bunch charge (nC)	primary e- 10 → 1	1	primary e- 8 → 0.4	1	0.5	1	primary e- 10 → 4	4
Norm. Emittance ($\gamma\beta\epsilon$) (μrad)	1400	310	1000	130	200/40 (Hor./Ver.)	150	100/15 (Hor./Ver.)	40/20 (Hor./Ver.)
Energy spread	0.125%	0.125%	0.5%	0.5%	0.16%	0.1%	0.16%	0.07%
Bunch / Pulse	2	2	2	2	2	2	2	2
Repetition rate	50 Hz		25 Hz		25 Hz		50 Hz	
Simultaneous top-up injection	3 rings (LER, HER, PF)		No top-up		Eventually		4+1 rings (LER, HER, DR, PF, PF-AR)	

Beam position jitter issue

- e+ target w/ small beam hole for e- beam ($\phi 2$ mm)
- Small beam hole could cause the beam position jitter.
- Machine study plan:
 - Remove e+ target in this summer shut down and install test dummy target w/ small hole of various diameter.
 - e+ target will be back in winter shutdown for Phase III



Schedule: Oct. 2018 -



- Pulsed bend (thermionic/rf gun merger line), some pulsed quads and steering installation in this summer shutdown
- Flux concentrator reinstallation during winter shutdown
- 50 Hz operation (will be tested in Dec. '18)



Summary

- Success of simultaneous injection to PF, PF-AR, HER, and LER from thermionic e- gun.
- Timing system for DR, pulsed quads and steering magnets work well.
- Success of HER injection via rf e- gun
- Required parameters for Phase II are almost achieved. e- emittance at BT and horizontal emittance of e+ after DR should be improved.
- Towards Phase III
 - Simultaneous top up injection with thermionic/RF e- gun
 - Pulsed bends and quads installation (in this summer shutdown)
 - High bunch charge and low emittance preservation
 - Beam line alignment (in this summer shutdown)
 - Beam jitter study w/o e+ target (in Oct. – Dec., 2018)
 - Beam orbit control study (in Oct. – Dec., 2018)

