

RF 電子銃の進展と入射器 の現状

周 翔宇

第118回Bファクトリー計画推進委員会
2020.9.30



Linac Beam Parameters for KEKB/SuperKEKB

Stage	KEKB (final)		Phase-I		Phase-II		Phase-III (interim)		Phase-III (final)	
Beam	e+	e-	e+	e-	e+	e-	e+	e-	e+	e-
Energy	3.5 GeV	8.0 GeV	4.0 GeV	7.0 GeV	4.0 GeV	7.0 GeV	4.0 GeV	7.0 GeV	4.0 GeV	7.0 GeV
Stored current	1.6 A	1.1 A	1.0 A	1.0 A	-	-	1.8 A	1.3 A	3.6 A	2.6 A
Life time (min.)	150	200	100	100	-	-	-	-	6	6
	primary e- 10		primary e- 8						primary e- 10	
Bunch charge (nC)	→ 1	1	→ 0.4	1	0.5	1	2	2	→ 4	4
Norm. Emittance	1400	310	1000	130	200/40		150/30	100/40	<u>100/15</u>	<u>40/20</u>
(gbe) (mmrad)					(Hor./Ver.)					
Energy spread	0.13%	0.13%	0.50%	0.50%	0.16%	0.10%	0.16%	0.10%	<u>0.16%</u>	<u>0.07%</u>
Bunch / Pulse	2	2	2	2	2	2	2	2	2	2
Repetition rate	50 Hz		25 Hz		25 Hz		50 Hz		50 Hz	
Simultaneous top-up injection (PPM)	3 rings (LER, HER, PF)		No top-up		Partially		4+1 rings (LER, HER, DR, PF, PF-AR)		4+1 rings (LER, HER, DR, PF, PF-AR)	






current stage

Pulse to pulse switching: rf e- gun/thermionic e- gun


Thermionic DC e- gun (GU_AT)

- e+ production e-: 10 nC (for LER injection)
- PF injection: 0.3 nC
- PF-AR injection: 0.3 nC




RF e- gun
R_A1 for HER inject
study/HER injection:

top up





CDS電子銃

- New Cavity
- New vacuum chamber




2020.9.25

Laser system development




- Oscillator and pulse pickers are synchronized with the RF signal
- Fiber structures with no cooling system





大型 DPSS モジュールへ交換 (2020.7)

- Final state Pump @ 808 nm 1.2 kW × 12=14.4 kW=3.6 J DPSS (2020.7)
- Output Power: $\omega(1030\text{ nm}):32\text{ mJ}$,
 $2\omega(515\text{ nm}):13\text{ mJ}$,
 $4\omega(257\text{ nm}):1.8\text{ mJ}$
1st line only



- ◆ 2 beam sources
- ◆ 1 – 25 Hz single/double bunches selectable
- ◆ Several month 24h/day running without maintenance

Laser transport line



Operating mode


Single laser injection

- For both guns

Two lasers injection

- High charge
- Source (1st) + Clean (2nd)
- $25(1^{st}) + 25(2^{nd}) = 50 \text{ Hz}$


- Monitoring all the laser situation and synchronization state.
- Remote control system
- Realize real time UV laser beam profile monitor
- Improve temperature stability in the laser hut
- Beam position monitor and auto feedback program



GR_A1用レーザーポジションフィードバック 制御システム (2020.9.24)

従来のやり方:


X/Yを手動調整




- 現在のレーザーポジション
- ポジションの変化履歴
- この範囲から外れるとフィードバックが動作する。

・ポジションの調整はA1地上ハット内のピエゾアジャスタ付きミラーマウントで行っている。

・実際のフィードバックは EPICS IOC で行っている。




フィードバック動作確認時のポジション




Profile reshaping (2019)




- Aperture of the beam illustrated



Laser spatial distribution



Phase space





- 秋運転から、2ndラインのみ
- ビーム径を調整

Reshaping of laser spatial distribution


1st line only (2020.7)

- Laser beam homogenizer: Diffractive optical element (**DOE**) for flat-top distribution
- Special compact vacuum chamber is designed, due to the micro structure is weak at dust
- ✓ No electrical discharge with high charge commissioning
- ✓ Laser beam stability is also improved
- ❑ Low emittance effect is expected
- × Beam size is fixed (For high charge)





DOE Basics : off-axis configuration

To avoid any zero order hot spot



The useful shaped pattern is deported off-axis to be separated from the focused zero order.




QE & Lifetime

	Off line	On line
Ir ₅ Ce	1.5×10^{-4}	1.5×10^{-5} (3-2)
Ir ₇ Ce ₂ + Heating (2018)	1.0×10^{-4}	1.5×10^{-5} (A1)
Ir ₂ Ce + Heating + Better vacuum (2019)	5.0×10^{-4}	2.0×10^{-4} (A1)
Ir ₇ Ce ₂ + Laser Clean (2020)	-	1.0×10^{-4} (A1)


The QE dependence of the laser energy

- QE decreasing by increase the laser energy



The QE transition of the time

- The QE drops rapidly, from about 50 hours after cleaning.
- After that, it appears to be gradually decreasing.




Bunch Charge feedback

2020/01/01 00:00:00 ~ 2020/07/11 00:00:00

KEKB e- (GR_A1) CHG Feedback (2020.4)

e- bunch charge (nC)



Conf

Configure KEKB e- (GR_A1) CHG F.B Parameter


monitor PV: SP_A1_G_1:ISNG	actuator PV: M_GND:LSR_ENG
monitor average [sec]: 5	output value: 0.009980645161
monitor update threshold: 1e-12	P: 0.009980645161
monitor update status: UPDATE	I: 0.000000000000
charge threshold pv: SP_A1_G_1:ISNG	D: 0.000000000000
charge threshold value: 0.1	actuator monitor PV: M_GND:LSR_ENG
monitor value: 0.698003870968	actuator monitor PV value: 120.475580573
target value: 0.7	High limit on output value: 1.0
Beam ON/OFF PV: SA:BEAM:KBE_GF	Low limit on output value: -1.0
beam on wait [sec]: 1.0	Proportional Gain: 5.0
Beam ON/OFF: ON	Integral Gain: 0.0001
actuator READY PV: A1_GND:LSR_EN	Derivative Gain: 0.0
actuator READY: READY	Feedback ON/OFF: ON
Feedback Status: Run	

Save Load

Close ON OFF

Graph

KEKB e- (GR_A1) CHG F.B Parameter Graph



Scale

Auto y1 max: 5 min: -5

Auto y2 max: 5 min: -5

Visible



monitor target output

Clear All Clear Half Close

- チャージ量が指定値となるよう、レーザーエネルギーを調整する
- 調整方法: 波長板を調整する。(自動・手動)

Laser cleaning / Focused laser size

- ◆ Irradiation of shorter-wavelength laser (2nd laser line only)
- ◆ Scan using focused laser beam without RF
- ◆ Laser cleaning works for recovering QE in maintenance day (every two weeks)
- ◆ Automatically running by program





量子効率MappingとLaser
Cleaningプログラムを開発した

常時Laser Cleaning On (量子効率の長寿命化)

1st line: $\sim 700\mu\text{J}$




2nd line (clean laser) : $300\mu\text{J}$



- Adjust the laser output energy to stabilize the charge
- Continuous laser cleaning between pulses
- No discharge (maybe due to DOE)
- Maintains at 2.5 nC


e- beam emittance (~ 1 nC)

- $\epsilon_{x,y} \sim 15 \mu\text{m}$ at Sector-B, Sector-C
- Emittance growth at BT2 in both directions.
- Emittance could be increased at around solenoid section in Sector1.




Steering magnet and BPM in solenoid section

- There is no BPM and steering magnet between e+ target and 16_5 unit.
- DC steering (x4) and BPM (x4) will be installed in this summer shutdown.
- It could be help to cure e+ beam loss and e- beam emittance growth.





e⁺ beam emittance (~ 1 nC)

- e⁺ beam emittance in linac and BT1 are smaller than current goal.
- Emittance growth at BT2 in both directions.



The reason for the emittance growth from BT2 is not clear.

More studies are needed.



FC assembly, base summary

	Phase 1	Phase 2	Phase 3	2019 autumn	2020 spring	2020 autumn	2021 winter~	delivery	removal	Present status (2020/6)	remark
Assembly 1	↔			←				Before 2015	2017/3	Tunnel	
Assembly 2		←						2016/3		Beam line	
Assembly 3		←	↔					2017/11		Test bench	
FC base 1								before 2015			Trial product
FC base 2								before 2015			Trial product
FC base 3	↔							before 2015	2017/3	Assembly 1	
FC base 4		↔							2018/9	Tunnel	
FC base 5		↔	←					2016/7	2020/9	Beam line for operation	
FC base 6			←					2017/11		Reserved	Hardening (Toyama)
FC base 7*				←				2019/10		Finished long term test	
FC base 8**					↔	←		2020/5		Under test	Final version modified
FC base 9**							←	2021/3		Under design	Final version spare

- *Base 7, 8, 9 (head : Cu → NC50, return yoke : SS400 → permendur)
- **Base 8, 9 Shape optimization (insulation, leakage magnetic field)

red: operation
blue: spare
black: test bench


Comparison FC base

	Material	Shape	Remark	For e-	For e+
Base 5 (in operation)	OFC + SS400	Old design	12 kA in beam line large slit gap	△	○
Base 7	NC50 + permendur	Old design	4.5 months test	○	○+ *
Base 8	NC50 + permendur	New design (optimized)	Cooling water leakage was found. (already fixed and tested during 4 days)	◎	○+ *


All FC bases achieve 12 kA in test stand. (*) return yoke (permendur) makes higher magnetic field.

Base 8


- Optimized yoke shape
- Reinforced insulation (FC head support)



Base 7 and older



Test result of new FC: 2020/1 – 2020/6




During long term test, no trouble (discharge and vacuum pressure problem)

FC base 7 test: ~ May 2020

FC base 8 test: June 2020 ~

Positron yield by FC (base 5) beam test

Y. Enomoto



Positron yield is 35% lower than the simulation.

- Differences between exp. and sim. conditions. (E/B field, primary beam direction/position, em shower sim. etc.)

The cause of the difference is not clear.

We've started a detailed investigation.

Ratio of bunch charge of positron at capture section exit to primary electron vs FC current.

There are no BPM and steering magnet until 17 m downstream of the target. (Only 6 acc. structures and solenoids)





2 stripline BPMs and 2 BPMs for e+ and 4 steering magnets will be installed in this summer.

Abnormal energy beam

- Collimator at ECS of linac end -

- Klystron down or rf phase trip could cause energy change.
- In the case of e⁺ beam, ECS (in linac end) can correct it to a certain extent. Beam can go through BT and into MR.
- To prevent such beam, collimator will be installed in this summer maintenance.



Summary

◆ Bunch charge

- Stable and enough bunch charge in this stage
- e-: 1.3 nC (from gun), 1.0 nC (linac end)
- e+: Primary e-: 11 nC (from gun), 9 nC (on W target), e+ : 2 nC (after target), 1.2 nC (linac end), 1.2 nC (BT)

◆ RF電子銃の進展

- 90° CDS銃を準備した
- DOE 導入 / 1st レーザー増強
 - ・ ジッターは全く無くなった
 - ・ カソード寿命が長寿命化
- 常時Laser Cleaning On (2nd専用レーザー)
 - ・ 1, 5 Hz で Inter Pulse Laser Cleaning 実施 (300 μ J)
 - ・ 2.5nC で維持でき
 - ・ Trigger システムを改造
- Position monitorを設置

◆ e+の進展

- FC入り替え (High bunch charge)
- SolenoidにSteering magnet と BPMを追加
 - ・ e⁺ビームの損失とe⁻ビームのエミッタンスの増加を解消する

Summary 2

◆ Beam abort 問題の改善

- Pulsed magnet misfire (orbit)
 - Control software have been improved.
- Install collimator at ECS (Linac end) in this summer shutdown.

◆ 50 Hz operationの対応

- Vertical pulsed bends and chambers will be replaced new one for 50 Hz operation of thermionic e- gun (LER, PF, PF-AR) in this summer shutdown.

◆ 問題点

- Emittance growth at BT2
- Reproducibility
- Low emittance w/ high bunch charge (~ 2 nC)